



# HANDLING & STORAGE

## Material Handling.

Precautionary measures taken in packaging, storage, transportation, and installation of R-Shield® MAX insulation products can help minimize the potential for damage from excessive solar exposure.

## Jobsite Storage.

Precautions taken when storing insulation products on the jobsite can help minimize the potential for damage. Keep product tarped or covered to protect from weather. Do not use clear plastic covering film. Care should be taken to keep exposed foam protected from reflective sunlight or prolonged solar exposure.

## Installation.

Precautions taken during the construction process can help minimize the potential for damage. Care should be taken to keep exposed foam protected from reflected sunlight or prolonged solar exposure. If deformation of the insulation product occurs due to excessive heat transferred from reflected and concentrated sunlight, remove the reflective surface or shield the insulation product.

A PRODUCT OF  
**PREMIER**  
BUILDING SYSTEMS



[www.rshieldinsulation.com](http://www.rshieldinsulation.com) | 800-766-3626

Copyright © 2022. R-Shield is a registered trademark of Premier Building Systems. RSI M04 08/22